


GENERAL NOTES

1. FINAL ORIENTATION AND TILT TO BE CONFIRMED ON SITE DURING COMMISSIONING. LUMINAIRE TILT TO BE LOCKED/FIXED FOLLOWING COMMISSIONING.
2. INSTALLATION SHALL ENSURE ZERO UPWARD LIGHT FROM LUMINAIRE TO ABOVE HORIZONTAL PLANE.
3. MAKE GOOD AND SEAL ALL PENETRATIONS TO BUILDING STRUCTURE TO MAINTAIN FIRE AND ACOUSTIC RATINGS.
4. LIGHTING CONTROL PANEL SHALL BE PROVIDED WITH 4 PUSH BUTTONS SET TO THE FOLLOWING:
 - SCENE 1 - AMATEUR COMPETITION/MATCH PRACTICE - 100% LP1-LP4
 - SCENE 2 - AMATEUR TRAINING - 50% LP1-LP4
 - LP1-LP4 OFF
 - SPARE
5. FINAL CONTROL SYSTEM CONFIGURATION AND TIME SCHEDULING TO BE CONFIRMED DURING COMMISSIONING BY CLUB REPRESENTATIVE. LUMINAIRES TO BE TURNED OFF DURING CURFEW FOR AS4282 COMPLIANCE.
6. DALI CONTROLLER SHALL BE CREATIVE LIGHTING EDIDIO OR APPROVED EQUAL.
7. REFER TO CIVIL/STRUCTURAL DOCUMENTATION FOR POLE FOOTING DETAILS. CONCRETE BASE SHALL BE RAISED MINIMUM 150mm ABOVE GRASS SURFACE.





LUMINAIRE DETAIL

THE DESIGN AND DETAILS SHOWN ON THESE DRAWINGS ARE APPLICABLE TO THIS PROJECT ONLY AND MAY NOT BE REPRODUCED IN WHOLE OR IN PART OR BE USED FOR ANY OTHER PROJECT OR PURPOSE WITHOUT THE WRITTEN PERMISSION OF ERBAS & ASSOCIATES WHICH COPYRIGHT RESIDES. ALL DIMENSIONS IN MILLIMETRES UNLESS OTHERWISE SHOWN. WORK TO FIGURED DIMENSIONS. DO NOT SCALE FROM DRAWINGS. CHECK ALL DIMENSIONS ON SITE PRIOR TO CONSTRUCTION. THIS DRAWING IS TO BE READ IN CONJUNCTION WITH ALL CONTRACT DOCUMENTS.

ISSUE	DATE	AMENDMENT
P1	30.10.20	PRELIMINARY ISSUE

ARCHITECT

CLIENT

BUILDING SERVICES ENGINEER
 Sydney Melbourne Manila L3, 116 Hardware St, Melbourne, VIC 3000 Ph: (03) 9111 2290 general@erbas.com.au www.erbas.com.au
DESIGNED TH
CHECKED PJ
NORTH POINT 

PROJECT
HEATHERTON OVAL LIGHTING

DRAWING TITLE			
ELECTRICAL SERVICES			
SITE PLAN			
SCALE of A1	PROJECT No.	DRAWING No.	ISSUE
1:400			
DATE			
OCT 2020			
DRAWN	MEL20266-E001		P1
JH			